

QUOTE

All amounts in CHF

CUSTOMER

Camille Renaud
Maison du Lac SA
Chemin des Tilleuls 14
1095 Lutry

PROJECT AND SCOPE

Living room renovation and fitted bookcase
Preparation, local insulation, ceiling work, wall furniture and finishing in the living room. Electrical work is outside this quote.

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
PREPARATION AND PROTECTION					
1	Site setup, protection and selective removal Full protection of retained routes, installation of protective boards and hand removal of linings that prevent measurement. Removed material stays sorted on site before disposal.	fixed	1	1'250.00	1'250.00
CEILING AND INSULATION					
2	Local insulation and vapour barrier Wood-fibre insulation with vapour barrier connected to accessible surfaces. Connections are made after a visual check of the existing support and before closing the ceiling.	m²	38.5	83.00	3'195.50
3	Counter-battened ceiling frame Laser-levelled counter-batten frame. This item includes normal packers and fixings, but not correction of a hidden structural defect in the support.	m²	55	71.00	3'905.00
FURNITURE AND FINISHING					
4	Oiled oak low bookcase Bookcase made from four fixed modules in oiled oak. Final dimensions follow the survey completed before ordering.	item	4	620.00	2'480.00

Atelier Pin Sàrl

Interior carpentry · Rue des Ateliers 8 · 1000 Lausanne · +41 21 555 01 14 · bonjour@atelier-pin.example · CHE-999.123.456 VAT

Quote EQ-2026-014

Revision 02

Published 14 October 2026

Valid through 13 November 2026

Quote continuation and technical descriptions

All amounts in CHF

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
4	Technical detail, continued from item 4 The oiled oak has a natural matt finish. Grain, colour and knot variation are part of the material. Visible edges receive the same finish. A sample is approved before ordering. The bookcase is installed on a dry, stable support. Fixing points follow the support survey. Any void, service or weakness found after opening is reported before work continues. Site references: survey dated 7 October 2026, sketch AP-14-B and oak sample EO-2.				
5	Installation, adjustment and finishing Installation includes assembly in the room, adjustment of any doors and local joint finishing. Clean-up removes the protection and installation offcuts.	h	58	82.00	4'756.00
6	Protection of retained elements Protection removed at the end of the work. This item is included with no separate price. INCLUDED, NO SEPARATE PRICE	—	—	—	—
OPTIONS AND EXCLUSIONS					
7	Integrated bookcase lighting Separate optional item and not included in the total. The price covers LED profiles and installation, not connection to the electrical panel or certification by an electrician. OPTIONAL, NOT INCLUDED IN TOTAL	fixed	1	3'680.00	3'680.00
8	Electrical-panel adaptation Excluded from this quote. Any panel adaptation, new circuit or electrical compliance work needs a separate offer from the customer's electrician. EXCLUDED	—	—	—	—

Included-line subtotal	CHF 15'586.50
Coordination discount	– CHF 780.00
VAT 8.1%	CHF 1'199.33
Total incl. VAT	CHF 16'005.83

CHE-999.123.456 VAT

PAYMENT AND ACCEPTANCE

Acceptance. Return this quote dated and signed by email before work starts. Acceptance confirms the scope, price and exclusions.

Payment. 40% on acceptance, 50% after furniture installation and 10% on handover. Payment is due in 15 days. No early-payment discount applies.

Price commitment. Fixed prices and quantities multiplied by unit prices make up the proposed price for the stated scope. They are not billed from a final measurement. Any approved change needs written agreement.

Programme and access. The customer provides access to the rooms on agreed dates and protects items not moved. Timing depends on material availability.