

## Atelier Pin Saràl

Interior carpentry · Rue des Ateliers 8 · 1000 Lausanne · +41 21 555 01 14 · [bonjour@atelier-pin.example](mailto:bonjour@atelier-pin.example) · CHE-999.123.456 VAT

## Quote EQ-2026-014

Revision 02

Published 14 October 2026

Valid through 13 November 2026

### PROPOSAL AT A GLANCE

## QUOTE

Living room renovation and fitted bookcase  
Preparation, local insulation, ceiling work, wall furniture and finishing in the living room. Electrical work is outside this quote.

#### BUSINESS

Atelier Pin Saràl  
Rue des Ateliers 8  
1000 Lausanne

#### CUSTOMER

Camille Renaud  
Maison du Lac SA  
Chemin des Tilleuls 14  
1095 Lutry

Quote EQ-2026-014 · Revision 02

Valid through 13 November 2026

#### TOTAL INCL. VAT

Included-line subtotal: CHF 15'586.50

Coordination discount: – CHF 780.00

VAT 8.1%: CHF 1'199.33

**CHF 16'005.83**

### PAYMENT AND ACCEPTANCE

**Acceptance.** Return this quote dated and signed by email before work starts. Acceptance confirms the scope, price and exclusions.

**Payment.** 40% on acceptance, 50% after furniture installation and 10% on handover. Payment is due in 15 days. No early-payment discount applies.

**Price commitment.** Fixed prices and quantities multiplied by unit prices make up the proposed price for the stated scope. They are not billed from a final measurement. Any approved change needs written agreement.

**Programme and access.** The customer provides access to the rooms on agreed dates and protects items not moved. Timing depends on material availability.

# Atelier Pin Sàrl

Interior carpentry · Rue des Ateliers 8 · 1000 Lausanne · +41 21 555 01 14 · [bonjour@atelier-pin.example](mailto:bonjour@atelier-pin.example) · CHE-999.123.456 VAT

## Quote EQ-2026-014

Revision 02

Published 14 October 2026

Valid through 13 November 2026

Detailed costing

All amounts in CHF

| ITEM                       | DESCRIPTION                                                                                                                                                                                                                               | UNIT           | QUANTITY | UNIT PRICE | AMOUNT          |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|----------|------------|-----------------|
| PREPARATION AND PROTECTION |                                                                                                                                                                                                                                           |                |          |            |                 |
| 1                          | <b>Site setup, protection and selective removal</b><br>Full protection of retained routes, installation of protective boards and hand removal of linings that prevent measurement. Removed material stays sorted on site before disposal. | fixed          | 1        | 1'250.00   | <b>1'250.00</b> |
| CEILING AND INSULATION     |                                                                                                                                                                                                                                           |                |          |            |                 |
| 2                          | <b>Local insulation and vapour barrier</b><br>Wood-fibre insulation with vapour barrier connected to accessible surfaces. Connections are made after a visual check of the existing support and before closing the ceiling.               | m <sup>2</sup> | 38.5     | 83.00      | <b>3'195.50</b> |
| 3                          | <b>Counter-battened ceiling frame</b><br>Laser-levelled counter-batten frame. This item includes normal packers and fixings, but not correction of a hidden structural defect in the support.                                             | m <sup>2</sup> | 55       | 71.00      | <b>3'905.00</b> |
| FURNITURE AND FINISHING    |                                                                                                                                                                                                                                           |                |          |            |                 |
| 4                          | <b>Oiled oak low bookcase</b><br>Bookcase made from four fixed modules in oiled oak. Final dimensions follow the survey completed before ordering.                                                                                        | item           | 4        | 620.00     | <b>2'480.00</b> |

# Atelier Pin Sàrl

Interior carpentry · Rue des Ateliers 8 · 1000 Lausanne · +41 21 555 01 14 · [bonjour@atelier-pin.example](mailto:bonjour@atelier-pin.example) · CHE-999.123.456 VAT

## Quote EQ-2026-014

Revision 02  
Published 14 October 2026  
Valid through 13 November 2026

### Detailed costing

All amounts in CHF

| ITEM                          | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | UNIT  | QUANTITY | UNIT PRICE | AMOUNT          |
|-------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----------|------------|-----------------|
| 4                             | <b>Technical detail, continued from item 4</b><br>The oiled oak has a natural matt finish. Grain, colour and knot variation are part of the material. Visible edges receive the same finish. A sample is approved before ordering. The bookcase is installed on a dry, stable support. Fixing points follow the support survey. Any void, service or weakness found after opening is reported before work continues. Site references: survey dated 7 October 2026, sketch AP-14-B and oak sample EO-2. |       |          |            |                 |
| 5                             | <b>Installation, adjustment and finishing</b><br>Installation includes assembly in the room, adjustment of any doors and local joint finishing. Clean-up removes the protection and installation offcuts.                                                                                                                                                                                                                                                                                              | h     | 58       | 82.00      | <b>4'756.00</b> |
| 6                             | <b>Protection of retained elements</b><br>Protection removed at the end of the work. This item is included with no separate price.<br><b>INCLUDED, NO SEPARATE PRICE</b>                                                                                                                                                                                                                                                                                                                               | —     | —        | —          | —               |
| <b>OPTIONS AND EXCLUSIONS</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |          |            |                 |
| 7                             | <b>Integrated bookcase lighting</b><br>Separate optional item and not included in the total. The price covers LED profiles and installation, not connection to the electrical panel or certification by an electrician.<br><b>OPTIONAL, NOT INCLUDED IN TOTAL</b>                                                                                                                                                                                                                                      | fixed | 1        | 3'680.00   | <b>3'680.00</b> |
| 8                             | <b>Electrical-panel adaptation</b><br>Excluded from this quote. Any panel adaptation, new circuit or electrical compliance work needs a separate offer from the customer's electrician.<br><b>EXCLUDED</b>                                                                                                                                                                                                                                                                                             | —     | —        | —          | —               |

|                        |                      |
|------------------------|----------------------|
| Included-line subtotal | CHF 15'586.50        |
| Coordination discount  | – CHF 780.00         |
| VAT 8.1%               | CHF 1'199.33         |
| <b>Total incl. VAT</b> | <b>CHF 16'005.83</b> |
| CHE-999.123.456 VAT    |                      |